



- KEY:**
- NEW FOOTWAY 100mm THICK COMPRISING 20mm AC6 DENSE SURF 100/150; BINDER COURSE REGULATING AREA - 50m²
 - EXISTING AREA OF FOOTWAY CONSTRUCTION TO BE SAW-CUT, BROKEN OUT AND DISPOSED OF TO TIP.
 - FOOTWAY INLAY 70mm THICK COMPRISING 20mm AC6 DENSE SURF 100/150 AND 50mm AC20 DENSE BIN 100/150 BINDER COURSE - AREA 44.6m²
 - EXISTING AREA OF FOOTWAY CONSTRUCTION TO BE SAW-CUT, BROKEN OUT AND DISPOSED OF TO TIP.
 - PCC FLAG FOOTWAY COMPRISING 65mm THICK CONCRETE FLAG, 30mm BEDDING SAND - AREA 56.4m²
 - EXISTING PCC FLAG FOOTWAY CONSTRUCTION TO BE REMOVED EXISTING CONSTRUCTION TO BE REMOVED INCLUDING LAYING COURSE (ASSUMED DEPTH 70mm). REPLACE WITH 20mm AC6 DENSE SURF 100/150 AND 50mm AC20 DENSE BIN 100/150 BINDER COURSE - AREA 70m²
 - PCC FLAG FOOTWAY COMPRISING 65mm THICK CONCRETE FLAG, 30mm BEDDING SAND - AREA 42.7m²
 - EXISTING AREA OF TACTILE PAVING INCLUDING LAYING COURSE TO BE TAKEN UP AND DISPOSED OF TO TIP.
 - TACTILE PAVING TO SCC STD. DRG. 1000/32 PROPOSED BUFF COLOURED TACTILE PAVING SLABS (400mm x 400mm x 50mm SLAB, 30mm SAND BEDDING) TOTAL AREA - 2.8m²
 - DUTCH ENTRANCE PRECAST CONCRETE KERB TOTAL LENGTH - 10m
 - TAKE UP AND DISPOSE PRECAST CONCRETE KERB. TOTAL LENGTH - 13m
 - HALF BATTERED SURFACE MOUNTED KERB - BOMAX SCAN KERB OR SIMILAR APPROVED TOTAL LENGTH - 68m
 - EXISTING GULLY TO BE DECOMMISSIONED
 - PROPOSED TRAP PC GULLY TYPE 1 IN ACCORDANCE WITH SCC STD 1000/360
 - GULLY CONNECTIONS SHALL BE 'RIDIGRAIN' TWIN WALL HDPE PIPE
 - MANCHESTER BOLLARD AT 3m CENTERS (OR SIMILAR APPROVED)
 - MANCHESTER BOLLARD SURFACE MOUNTED AT 3m CENTERS (OR SIMILAR APPROVED)
 - CAST IRON BELL BOLLARD (FURNITUBES BELL 150 OR SIMILAR APPROVED)

Notes

Rev.	Description	Drwn	Sig.	Date	Chkd	Sig.	Date	Appr	Sig.	Date

Rev.	Description	Drwn	Sig.	Date	Chkd	Sig.	Date	Appr	Sig.	Date

North Point

Based upon the Ordnance Survey mapping with the permission of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings. Surrey County Council LA 076872 2002.

Drawn by	Sig.	Date
PG	PG	JUNE 2022
Checked by	Sig.	Date
AP	AP	NOV 2022
Approved by	Sig.	Date
DS	DS	NOV 2022

Project: CLARENDON PRIMARY SCHOOL
KNAPP ROAD, ASHFORD

Drawing: SAFETY OUTSIDE SCHOOL
GENERAL ARRANGEMENTS

SHEET 1 OF 1

Project No. PC1256

Contract Sheet No. 1256-01

Rev. -

Classification: CONSTRUCTION