

# PHASE 1A

1:200 @ A4



SCHOOL LANE

DIAG 1004  
WIDTH 100mm  
GAP 2000mm  
LENGTH 10.0m  
COLOUR WHITE

DIAG 1009A  
WIDTH 100mm  
GAP 300mm  
LENGTH 4.0m  
COLOUR WHITE

DIAG 1003A  
WIDTH 100mm  
GAP 300mm  
LENGTH 5.5m  
COLOUR WHITE


PROPOSED BUFF COLOURED TACTILE PAVING SLABS (400MM X 400MM) FOR UNCONTROLLED PEDESTRIAN CROSSING FACILITY TO BE INSTALLED - TOTAL AREA/NO. - 0.96M<sup>2</sup>/6 NO. SLABS

PROPOSED FOOTWAY CONSTRUCTION ON EXISTING CARRIAGEWAY EXTENTS (20MM SURFACE COURSE; 50MM BINDER COURSE; BINDER COURSE REGULATING) - TOTAL AREA - 1M<sup>2</sup>

PROPOSED BUFF COLOURED TACTILE PAVING SLABS (400MM X 400MM) FOR UNCONTROLLED PEDESTRIAN CROSSING FACILITY TO BE INSTALLED - TOTAL AREA/NO. - 0.96M<sup>2</sup>/6 NO. SLABS

### KEY - PROPOSED KERBING WORKS

- BN(i) PROPOSED FULL HEIGHT BULLNOSED KERBS (STRAIGHT) TO BE INSTALLED AT 115mm UPSTANDS / AND TO TIE INTO EXISTING FULL HEIGHT KERB UPSTANDS - TOTAL LENGTH: 5.8m
- BN(ii) PROPOSED BULLNOSED TRANSITION KERBS (STRAIGHT) TO BE INSTALLED AT 115mm UPSTANDS DOWN TO 6mm KERB UPSTANDS - TOTAL LENGTH: 0.9m
- BN(iii) PROPOSED FULL HEIGHT BULLNOSED KERBS (STRAIGHT) TO BE INSTALLED AT 6mm UPSTANDS / AND TO TIE INTO EXISTING FULL HEIGHT KERB UPSTANDS - TOTAL LENGTH: 4.5m



Notes

Rev.	Description	Drwn	Sig.	Date	Chkd	Sig.	Date	Appr	Sig.	Date

North Point



Based upon the Ordnance Survey mapping with the permission of the Controller of Her Majesty's Stationery Office © Crown copyright. Unauthorised reproduction infringes Crown copyright and may lead to prosecution or civil proceedings.  
Surrey County Council Ltd 02/08/22, 2022.

Drawn by SA SA Date 07/2023

Checked by originator SA SA Date

Approved by SA SA Date

Project

Drawing

Road Safety outside Schools Schemes  
Year 2 (2023/2024)  
Puttonham C of E School  
School Lane / The Street (Phase 1A)

### SAFETY, HEALTH AND ENVIRONMENTAL INFORMATION

In addition to the hazards/risks normally associated with the types of work detailed on this drawing, note the following significant residual risks. (Reference shall also be made to the Design Hazard Log)

CONSTRUCTION
MAINTENANCE/CLEANING
USE
DECOMMISSIONING/DEMOLITION

If it is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement.

Project No. 4D621001

Contract Sheet No.

Drawing No. PH1A

Rev. -

Classification CONSTRUCTION